

**SECTION 096566 --- RESILIENT ATHLETIC FLOORING****PART 1-GENERAL****1.1 DESCRIPTION**

- A. This document specifies the complete installation of a rubber surface system designed for multiple sport use, as formulated by Horner Flooring Company.
- B. The concrete contractor shall provide a concrete slab, smooth troweled and level to a tolerance of 1/8" (3mm) in a 10'0" (3m) radius, subject to the approval of the flooring contractor. LABOR AND MATERIALS NECESSARY TO PUT THE CONCRETE SLAB IN ACCEPTABLE CONDITION (HIGH AREAS GROUND DOWN AND LOW AREAS FILLED WITH APPROVED LEVELING COMPOUNDS) SHALL BE THE RESPONSIBILITY OF THE CONCRETE CONTRACTOR.
  - 1. Membrane waterproofing
    - a. Concrete subfloors on or below grade shall be adequately waterproofed beneath and at the perimeter walls and on earth side of below grade walls. It is the responsibility of the engineer to determine the extent of this need.
  - 2. Concrete subfloors shall have an adequate vapor retarder beneath and at the perimeter of the slab.
  - 3. No pea gravel, river gravel or slag aggregate shall be allowed in the concrete. The concrete strength range at the time of wood flooring installation shall be between 3,000 PSI and 3,500 PSI.

**1.2 QUALITY ASSURANCE**

- A. Supplier Qualifications
  - 1. Supplier of flooring shall be Horner Flooring Company.
  - 2. Basis of design shall be "EcoTrack" sports floor system as provided by Horner Flooring, [www.hornerflooring.com](http://www.hornerflooring.com), (800-380-0119).
  - 3. Materials other than those listed must be approved 10 days prior to bid date by written addendum. Materials from non-approved manufacturers will not be accepted.
- B. Installer Qualifications
  - 1. The flooring contractor shall be a Horner Accredited Installation Company on-site for the duration of the wood floor installation; or, a contractor approved by Horner Flooring.
- C. Flooring materials shall never be stored outdoors or exposed to outdoor elements in transport or storage.

**1.3 WORKING CONDITIONS**

- A. The floor system shall not be delivered or installed until the concrete slab is properly cured and all masonry, plastering, tile work and overhead mechanical trades are completed and building is permanently enclosed and weathertight.
- B. Flooring installation shall not begin until all sub-contract work which would cause damage, dirt, dust or interruption of normal installation pace is completed. Subfloors shall be clean, dry and free from dirt, dust, oil, grease, paint, alkali, concrete curing agents, hardening and parting compounds, old adhesive residue, or other foreign materials.
- C. Moisture content of the concrete slab must not exceed 3 pounds per 1,000 square feet (1kg per 68 m<sup>2</sup>) over 24 hours when using the calcium chloride test as per ASTM 1869-98.
- D. The installation area shall be closed to all traffic and activity for a period to be set by the flooring contractor.
- E. Permanent heat, light, and ventilation shall be installed and operating prior to, during and after installation. HVAC System shall be operating in balance at levels and conditions consistent with those during permanent occupancy.
- F. If the material is to be stored prior to installation, the general contractor shall provide an area where the stored materials can be maintained at a minimum of 55° F (13° C) and relative humidity under 50%.
- G. One week prior to, during and for 168 hours after installation, a room temperature of 65° F (18° C) or more and 35% relative humidity or less shall be maintained.
- H. Adhere to all MSDS requirements for materials employed in the work. Protect all persons from exposure to hazardous materials.
- I. After synthetic floors have been fully installed, the floor area is to be kept locked by general contractor for a minimum of 120 hours to allow curing time for system. No other trades or personnel are allowed on floor until accepted by the owner in writing.

## 1.4 WARRANTY

- A. Horner Flooring Company hereby warrants the flooring materials to be free from manufacturing defects for a period of 1 year from the date of substantial completion. This warranty is expressly limited to the flooring materials supplied by Horner. This warranty is in lieu of all other warranties, expressed or implied including but not limited to any warranty of merchantability or fitness for a particular purpose, and of any other obligations on the part of Horner. This warranty does not cover floor damage caused by conditions beyond our control, such as fire, wind, floor surface chemical action, faulty maintenance, improper ventilation, faulty construction of building, Act of God, ordinary wear and tear, excess moisture and excess dryness, separation of concrete slab, settlement of walls, failure of floor if not installed properly, when installed over poured urethane or other previously existing floors if poured urethane returns to its liquid state, if previously existing floors release from concrete slab. In the event of breach of any warranty, the liability of Horner shall be limited to repairing or replacing material and system components supplied by Horner and proven to be defective in manufacture, and shall not include any other damages, either direct or consequential.
- B. Extended warranties are based on maintenance and yearly/annual cleaning and recoating agreements with certified contractors.

## PART 2-PRODUCTS

### 2.1 MATERIAL

- A. All components shall be non-hazardous and not contain ANY lead, mercury, nor any heavy metals, PCB, or formaldehyde and shall be supplied by Horner Flooring Company.
- B. EcoTrack Adhesive is a one component adhesive shall be supplied by Horner Flooring Company. No substitutions. Use of non-approved adhesives shall void warranty.
- C. EcoTrack is a homogeneous, non-layered rolled rubber product consisting of recycled rubber tires and urethane binder.
  - 1. Thickness: 3/8" (10mm) Standard  
OPTION: Thickness may be 1/2" (12mm)
  - 2. Width: 36" (916mm)  
OPTION: Width may be 42" (1069mm) or 48" (1219mm)
  - 3. Length: ~50' depending upon width and thickness specified.
- D. Physical Properties
  - 1. Density: .75 g/m<sup>3</sup> ASTM D 297
  - 2. Tensile Strength: 116 psi minimum ASTM D 412, Die C
  - 3. Compression: ASTM F 36
    - a. 50 psi – 15% 81%
    - b. 100 psi – 28% 92%
    - c. 200 psi – 45% 95%
  - 4. Shore A Hardness: 50+- 5 ASTM D 2240
  - 5. Tear: 30 ppi ASTM D524, Die C
  - 6. Flexibility: 0-1 Factor ASTM F
  - 7. Compression Set B (25% deflection, 22 hours, 158 Degrees): 26% ASTM D395
- E. EcoTrack Game Line Paint shall be approved by Horner Flooring Company and must be compatible with rubber sports track.
- F. OPTION: Vinyl wall base 4" (102mm) high; select color: black or brown.

## PART 3-EXECUTION

### 3.1 INSPECTION

- A. Inspect concrete slab for proper tolerance and dryness and report any discrepancies to the general contractor for correction.
- B. The concrete slab shall be cleaned of all debris so flooring contractor will have adequate access to work surface.
- C. All overhead work and wet trades shall be complete in floor work area.
- D. Installer shall document all working conditions provided in general specifications before installation begins.

**3.2 INSTALLATION**

- A. Ecotrack Rubber Track
  - 1. Unroll and allow to relax before cutting and fitting.
  - 2. Thoroughly mix the urethane adhesive according to manufacturer's instructions. Use manufacturer's notched trowel with specified dimension to spread adhesive.
  - 3. Unroll rubber track into freshly applied adhesive.
  - 4. Roll the entire track with a medium-sized steel roller to remove entrapped air.
  - 5. Wipe away adhesive that oozes between seams with wood alcohol.
- B. Game Line Paint
  - 1. Paint game lines in accordance with manufacturer's current procedures using approved material.

**3.3 VINYL WALL BASE - OPTION**

- A. Install Vent Cove Base, mitering inside corners and anchoring to walls with base cement or screws and anchors.

**3.4 PROTECTION**

- A. No traffic or other trades shall be allowed on the surface for a period of one week (168 hours) following installation to allow for complete curing of the finish.
- B. No smoking, open flames, or sparks from electrical equipment or other sources shall be permitted during application of materials

**3.5 MAINTENANCE**

- A. Upon completion of floor installation, the owner, attendants or individuals in charge and responsible for the upkeep of the building are to see that the care and maintenance instructions outlined within the provided Horner Care and Maintenance Manual are followed. Horner Flooring and certified dealers may offer extended warranty and maintenance agreements. It is recommended that any extended agreements include maintenance and recoats by the original installing contractor or related/recommended parties. (See maintenance/cleaning and recoating information on Horner Flooring website).

**END OF SECTION**